

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-19025-00-01
Spot: NWSWSENE Sec/Twnshp/Rge: 6-26S-11W
3293 feet from S Section Line, 1024 feet from E Section Line
Lease Name: DENISTON Well #: 3
County: PRATT Total Vertical Depth: 4380 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	13.375	178		WITH 175 SX CMT
PROD	7	4379	1430	WITH 175 SX CMT
SURF	9.625	988		WITH 275 SX CMT

Well Type: SWD UIC Docket No: E14489.1 Date/Time to Plug: 07/05/2018 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 617-4671

Proposed Plugging Method: SAND BACK 50' ABOVE PERFS & 7 SX CMT. PLUG AT 1050' WITH 20 SX GEL & 75 SX CMT. PLUG AT 300' WITH 75 SX CMT. PLUG AT 40' WITH 30 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/06/2018 12:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4050' & PUT 7 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 1050' WITH 20 SX GEL & 75 SX CMT. 2ND PLUG AT 310' WITH 75 SX CMT. 3RD PLUG AT 40' WITH 100 SX CMT. TOP OFF WITH 25 SX CMT. HOLE ON VACUUM. 7/6/18: TAG TOP OF CMT AT 750' & FOUND FLUID AT 700'. RUN TBG INTO 300'. LOAD HOLE & SPOT 75 SX CMT. PULLED TO 60' & CIRCULATE CMT TO SURFACE WITH 60 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4281	4382		
4124	4128		


INVOICED
AUG 03 2018

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

Signed


(TECHNICIAN)

RECEIVED
JUL 23 2018
KCC DODGE CITY

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 02 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

KMS