

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-075-20042-00-00
Spot: W2W2SESW Sec/Twnshp/Rge: 21-24S-41W
641 feet from S Section Line, 3734 feet from E Section Line
Lease Name: SCOTT Well #: 2
County: HAMILTON Total Vertical Depth: 2380 feet

Operator License No.: 30425
Op Name: DNR OIL AND GAS, INC.
Address: 12741 E CALEY UNIT 142
CENTENNIAL, CO 80111

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		750		
PROD	4.5	2378	0	WITH 200 SX CMT
SURF	8.625	365		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/12/2018 1:00 PM
Plug Co. License No.: 34367 Plug Co. Name: LONESTAR SERVICES LLC
Proposal Rcvd. from: LARRY ROMME Company: LONESTAR SERVICES LLC Phone: (620) 626-7100

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/12/2018 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

RUN TBG TO 1858' & SPOT 60 SX CMT UP TO 850'. FULL CIRCULATION. (FILL UP IS OVER PERFS DUE TO GLORIETTA CASING LEAK). SET CIBP @ 750'. TEST CASING TO 700#. HOLDING. PERFORATE 4 HOLES AT 700'. INJECTION RATE 2 BPM AT 150#. CIRCULATE CMT TO SURFACE USING 225 SX CMT LEAVING THE 4 1/2" CASING & 4 1/2" X 8 5/8" ANNULUS FULL OF CMT FROM 700' TO 0'.

Top	Bot	Thru	Comments
2334	2336		


INVOICED
AUG 03 2018

Remarks: USED 60/40 POZMIX 4% GEL BY GRESSEL.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED
JUL 24 2018
KCC DODGE CITY



RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

AUG 02 2018

CONSERVATION DIVISION
WICHITA, KS

Handwritten mark