

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-075-20041-00-00
Spot: SWNESWSE Sec/Twnshp/Rge: 20-24S-41W
851 feet from S Section Line, 1718 feet from E Section Line
Lease Name: OVERTON Well #: 1
County: HAMILTON Total Vertical Depth: 2365 feet

Operator License No.: 30425
Op Name: DNR OIL AND GAS, INC.
Address: 12741 E CALEY UNIT 142
CENTENNIAL, CO 80111

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2365	0	WITH 200 SX CMT
SURF	8.625	375		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/11/2018 9:00 AM
Plug Co. License No.: 34367 Plug Co. Name: LONESTAR SERVICES LLC
Proposal Rcvd. from: LARRY ROMME Company: LONESTAR SERVICES LLC Phone: (620) 626-7100

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/11/2018 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 150# HULLS & 80 SX CLASS A CMT WITH 3% CC VIA 4 1/2" CASING. DISPLACE TO 1200' WITH WATER. BOTTOM OF PLUG IS AT 2330'. 4 1/2" CASING DEVELOPED A LEAK DURING DISPLACEMENT BOTTOM OF CMT AT 2330'. TAG TOC WITH WIRELINE AT 1168'. PERFORATE 4 HOLES AT 700'. RUN TBG & PACKER TO 450'. PUMP INTO PERFS AT 1 1/2 BPM AT 200#. GOT CIRCULATION OUT 4 1/2" X 8 5/8" ANNULUS. TIH WITH TBG (NO PACKER) TO 724' & CIRCULATE CMT TO SURFACE UP TO 4 1/2" & THROUGH PERFS UP THE 4 1/2" X 8 5/8" ANNULUS WITH 225 SX CMT. TOOH WITH TBG & TOP OFF WITH 30 SX CMT.

Perfs:


Top	Bot	Thru	Comments
2328	2380		

INVOICED
AUG 03 2018

Remarks: USED CLASS A CEMENT & 3% CC & 60/40 POZMIX 4% GEL BY GRESSEL.

Plugged through: TBG

District: 01

Signed 
(TECHNICIAN)

RECEIVED
JUL 24 2018
KCC DODGE CITY

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 02 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

pms