

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-075-20039-00-00
Spot: SWNESENW Sec/Twnshp/Rge: 28-24S-41W
3314 feet from S Section Line, 3167 feet from E Section Line
Lease Name: GREGORY-TATE Well #: 1
County: HAMILTON Total Vertical Depth: 2374 feet

Operator License No.: 30425
Op Name: DNR OIL AND GAS, INC.
Address: 12741 E CALEY UNIT 142
CENTENNIAL, CO 80111

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2374	0	WITH 200 SX CMT
SURF	7	350		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/11/2018 4:00 PM
Plug Co. License No.: 34367 Plug Co. Name: LONESTAR SERVICES LLC
Proposal Rcvd. from: LARRY ROMME Company: LONESTAR SERVICES LLC Phone: (620) 626-7100

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/12/2018 12:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

7/11/18: PUMP 150# HULLS & 80 SX CLASS A CMT DOWN 4 1/2" CASING. DISPLACE TO 1200'. WELL DID NOT PRESSURE UP. 7/12/18: TAG TOC WITH WIRELINE AT 1495'. BOTTOM OF CMT AT 2346'. TEST CASING TO 600#. HOLDING. PERFORATE 4 HOLES AT 680'. INJECTION RATE 1 1/2 BPM AT 200#. CIRCULATE CMT TO SURFACE WITH 225 SX CMT. TOP OFF WITH 5 SX CMT LEAVING THE 4 1/2" CASING & 4 1/2" X 7" ANNULUS FULL OF CMT FROM 680' TO 0'.

Top	Bot	Thru	Comments
2344	2346		

INVOICED
AUG 03 2018

Remarks: USED 60/40 POZMIX 4% GEL & CLASS A CEMENT WITH 3% CC BY GRESSEL.

Plugged through: TBG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
JUL 24 2018
KCC DODGE CITY

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

AUG 02 2018

CONSERVATION DIVISION
WICHITA, KS

KMS