

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-093-00225-00-00  
Spot: NWSEWSE Sec/Twnshp/Rge: 12-22S-35W  
1957 feet from S Section Line, 1935 feet from E Section Line  
Lease Name: SUDAN Well #: 1  
County: KEARNY Total Vertical Depth: 2750 feet

Operator License No.: 31004  
Op Name: BONE, SALLY L.  
Address: PO BOX 97  
WOODLAND PARK, CO 80866

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1025		
CIBP		2000		WITH 4 SX CMT
PROD 7		2555	0	WITH 100 SX CMT
SURF	10.75	220		WITH 175 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/12/2018 9:30 AM  
Plug Co. License No.: 8438 Plug Co. Name: POST & MASTIN WELL SERVICE, INC.  
Proposal Rcvd. from: DAVID BONE Company: SALLY BONE Phone: (620) 287-4511

Proposed Plugging Method: SET CIBP @ 2000' WITH 4 SX CMT. SET CIBP @ 1025'. CHECK CASING INTEGRITY. PERFORATE AT 1000'. RUN TBG & PACKER TO 750'. PUMP 80 SX CMT IN AND OUT PLUG WITH 1 SX HULLS IN LAST 40 SX CMT. PERFORATE AT 250'. RUN 1 JOINT TBG WITH PACKER. CIRCULATE CMT IN & PUT 7" X 10 3/4" ANNULUS LEAVING FULL.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/12/2018 6:30 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

Perfs:

SET CIBP @ 2000' WITH 4 SX CMT. SET CIBP @ 1025'. PRESSURE TO 600#. PERFORATE AT 1000'. RAN TBG & PACKER TO 750'. PUMP 80 SX IN AND OUT PLUG WITH 1 SX HULLS IN LAST 40 SX CMT. POOH WITH TBG & PACKER. PERFORATE AT 250'. RAN 1 JOINT TBG & PACKER. CIRCULATED CMT TO SURFACE WITH 125 SX CMT. TOPPED OFF WITH 10 SX CMT.

Top	Bot	Thru	Comments
2555	2610	OH	

INVOICED  
AUG 03 2018


Remarks: \*\*COMPLIANCE ISSUE: DENIED TA HIGH FL\*\* USED 60/40 POZMIX 4% GEL BY QES.

Plugged through: CSG

District: 01

RECEIVED  
JUL 23 2018  
KCC DODGE CITY

Signed




(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

AUG 02 2018

CONSERVATION DIVISION  
WICHITA, KS

  
Form CP-2/3