

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-24029-00-00
Spot: NENWSWNW Sec/Twnshp/Rge: 24-31S-13W
1584 feet from N Section Line, 636 feet from W Section Line
Lease Name: PACKARD Well #: 24-1
County: BARBER Total Vertical Depth: 4739 feet

Operator License No.: 34886
Op Name: TOTO ENERGY, LLC
Address: 25815 OAK RIDGE DR
SPRING, TX 77380

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4190		WITH 2 SX CMT
PROD	5.5	4475	2024	WITH 250 SX CMT
SURF	8.625	428		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/19/2018 3:00 PM
Plug Co. License No.: 34422 Plug Co. Name: RED ROCK ENERGY SERVICES INC.
Proposal Rcvd. from: TIM MYERS Company: TOTO ENERGY Phone: (603) 724-1675

Proposed Plugging Method: CIBP @ 4190' WITH 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 70 SX CMT. PLUG AT 240' WITH 30 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/19/2018 4:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4190' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 602' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 433' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4334	4348		
4312	4328		
4286	4294		
4240	4280		

INVOICED
AUG 03 2018

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
JUL 23 2018
KCC DODGE CITY

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 02 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

kms