

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-21812-00-00
Spot: E2NWNE Sec/Twnshp/Rge: 2-16S-27W
4877 feet from S Section Line, 1676 feet from E Section Line
Lease Name: OFFNER/CURTIS Well #: 1
County: LANE Total Vertical Depth: 4480 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		1950		460 SX CMT, ADDITIONAL CEMENT OF 100 SX.
PROD	5.5	4471	0	WITH 175 SX CMT
SURF	8.625	223		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/13/2018 9:00 AM
Plug Co. License No.: 5135 Plug Co. Name: FARMER, JOHN O., INC.
Proposal Rcvd. from: VAL DREHER Company: FARMER, JOHN O., INC. Phone: (785) 483-8356

Proposed Plugging Method: RUN TBG TO BOTTOM PUMP 50 SX CMT & 150# HULLS. CIRCULATE CMT TO SURFACE FROM 2000'.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/13/2018 2:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4384' & PUMPED 48 BBL GEL WATER THEN 75 SX CMT & 300# HULLS. PULL TBG TO 2000' & PUMPED 250 SX CMT. CMT CIRCULATED TO SURFACE. PULL TBG & TOPPED OFF WITH 15 SX CMT. TIED ONTO BACKSIDE & PRESSURED TO 300#.

Perfs:

Top	Bot	Thru	Comments
4388	4396		
4067	4072		
4042	4048		
3878	3882		


INVOICED
AUG 03 2018

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED
JUL 20 2018
KCC DODGE CITY

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 02 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

KMS