

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-165-21742-00-00
Spot: NWNE SWNW Sec/Twnshp/Rge: 23-16S-20W
3692 feet from S Section Line, 4350 feet from E Section Line
Lease Name: NORTH Well #: 1
County: RUSH Total Vertical Depth: 3950 feet

Operator License No.: 34134
Op Name: TREK RESOURCES, INC.
Address: 4925 GREENVILLE AVE., STE 915
DALLAS, TX 75206

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		2110		WITH 225 SX CMT
PROD	5.5	3945	0	WITH 175 SX CMT
SURF	8.625	216		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/22/2018 11:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 35 SX CMT & 150# HULLS THEN GEL SPACER TO 1400' THEN CMT TO SURFACE. FILL BACKSIDE WITH CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: PARTIAL
Date/Time Plugging Completed: 06/27/2018 2:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

6/22/18: WHILE PULLING TBG, PACKER GOT STUCK AT 2750'. COULD NOT GET FREE. TIED ONTO TBG & PUMPED 50 SX CMT & 150# HULLS TO BOTTOM. SHUT DOWN. 6/27/18: SHOT TBG OFF AT 1990' & SPOTTED 2 SX CMT. PULLED TBG TO 1400' & MIXED 140 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 25 SX CMT. TIED ONTO BACKSIDE & MIXED 15 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
3884	3886		

INVOICED

AUG 03 2018

Remarks: USED 60/40 POZMIX 4% GEL BY QUALTY WELL SERVICE.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED
JUL 26 2018
KCC DODGE CITY



RECEIVED
KANSAS CORPORATION COMMISSION

AUG 02 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

Handwritten initials