

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-23625-00-00
Spot: SESESWSW Sec/Twnshp/Rge: 25-16S-22W
327 feet from S Section Line, 4269 feet from E Section Line
Lease Name: UMMEL RANCH Well #: 1
County: NESS Total Vertical Depth: 4400 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		1700		WITH 210 SX CMT
PROD	5.5	4392	0	WITH 125 SX CMT
SURF	8.625	265		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/25/2018 1:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: LANCE FELLHOELTER Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: PUMP 50 SX CMT WITH 200# HULLS ON BOTTOM. CIRCULATE CMT TO SURFACE FROM 1750'. PRESSURE BACKSIDE TO 300#.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/25/2018 4:15 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

RAN TBG TO 4200' & PUMPED 50 SX CMT WITH 200# HULLS. PULLED TBG TO 1750' & CIRCULATED CMT TO SURFACE WITH 210 SX CMT. PULLED TBG & TOPPED OFF WITH 20 SX CMT. TIED ONTO BACKSIDE & PRESSURED TO 300# WITH 20 SX CMT.

Top	Bot	Thru	Comments
4271	4274	CSG	

INVOICED
AUG 03 2018

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed _____
(TECHNICIAN)

RECEIVED
JUL 27 2018
KCC DODGE CITY

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 02 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

KMS