

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-165-21939-00-00
Spot: NESESE Sec/Twnshp/Rge: 10-16S-20W
990 feet from S Section Line, 330 feet from E Section Line
Lease Name: CUMBERLAND A Well #: 1-10
County: RUSH Total Vertical Depth: 3902 feet

Operator License No.: <u>9408</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>TRANS PACIFIC OIL CORPORATION</u>	PC		1395		WITH 150 SX CMT
Address: <u>100 S MAIN STE 200</u>	PROD	5.5	3898	0	WITH 120 SX CMT
<u>WICHITA, KS 67202</u>	SURF	8.625	690		WITH 400 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/24/2018 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: MONTE BOYDSTON Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 75 SX CMT & 300# HULLS. PULL TBG TO 1400' & CIRCULATE CMT. PULL TBG & TOP OFF. FILL BACKSIDE WITH CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE
Date/Time Plugging Completed: 07/24/2018 4:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RAN TBG TO 3800' & MIXED 75 SX CMT & 300# HULLS. PULLED TBG TO 1750' & MIXED 200 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 20 SX CMT. TIED ONTO BACKSIDE & PUMPED 15 SX CMT & PRESSURED TO 300#. CASING WAS STILL FALLING. WAITED 3 HOURS. TOPPED OFF WITH 50 SX CMT. CASING STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
3898	3902	OH	

INVOICED
AUG 03 2018

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
JUL 26 2018
KCC DODGE CITY

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 02 2018
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

KMS