

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-083-10044-00-01
Spot: NWNW Sec/Twnshp/Rge: 18-21S-22W
4479 feet from S Section Line, 4479 feet from E Section Line
Lease Name: COSSMAN Well #: 2
County: HODGEMAN Total Vertical Depth: 4451 feet

Operator License No.: 32331
Op Name: DK OPERATING INC.
Address: 621 BENTON ST.
JETMORE, KS 67854

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4200		WTH 2 SX CMT
CIBP		4300		
PROD	5.5	4446	0	WITH 100 SX CMT
SURF	8.625	286		200 SX CMT.

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/26/2018 1:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: RICK POPP Company: POPP OPERATING Phone: (620) 786-5514

Proposed Plugging Method: CIBP @ 4200' WITH 2 SX CMT. PRESSURE CASING. RUN BOND LOG.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: NONE
Date/Time Plugging Completed: 07/26/2018 4:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4200' WITH 2 SX CMT. PRESSURE TEST THE CASING TO 500# HELD. RAN BOND LOG. FOUND CMT FROM 1500' TO 0'. RAN TBG TO 1550' & CIRCULATED CMT TO SURFACE WITH 155 SX CMT. PULLED TBG & TOPPED OFF WITH 5 SX CMT. BACKSIDE WAS FULL.

Perfs:

Top	Bot	Thru	Comments
4282	4286		
4276	4278		
4270	4272		

INVOICED
AUG 03 2018

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

RECEIVED
JUL 27 2018
KCC DODGE CITY

Signed Michael Maier
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 02 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

KMS