

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-083-20182-00-01
Spot: NWSEWSW Sec/Twnshp/Rge: 29-23S-21W
650 feet from S Section Line, 667 feet from W Section Line
Lease Name: AISTRUP Well #: 1
County: HODGEMAN Total Vertical Depth: 4673 feet

Operator License No.: 32331
Op Name: DK OPERATING INC.
Address: 621 BENTON ST.
JETMORE, KS 67854

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4390		WITH 2 SX CMT
PROD	5.5	4431	0	WITH 500 SX CMT
SURF	8.625	268		WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/25/2018 10:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: RICK POPP Company: POPP OPERATING Phone: (620) 786-5514

Proposed Plugging Method: CIBP 50' ABOVE PERFS WITH 2 SX CMT. CIRCULATE CMT TO SURFACE FROM 1500'. TOP OFF & CHECK BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/25/2018 12:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

SET CIBP @ 4390' WITH 2 SX CMT. RUN TBG TO 1483' & MIXED 175 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 10 SX CMT. TIED ONTO BACKSIDE & PUMPED 5 SX CMT. PRESSURED TO 300#.

Top	Bot	Thru	Comments
4431	4450	OH	

INVOICED
AUG 03 2018

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED
JUL 26 2018
KCC DODGE CITY



RECEIVED
KANSAS CORPORATION COMMISSION

AUG 02 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

KMS