

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-083-20864-00-02
Spot: NWSENWSW Sec/Twnshp/Rge: 29-23S-21W
1964 feet from S Section Line, 684 feet from W Section Line
Lease Name: AISTRUP Well #: 2
County: HODGEMAN Total Vertical Depth: 4654 feet

Operator License No.: 32331
Op Name: DK OPERATING INC.
Address: 621 BENTON ST.
JETMORE, KS 67854

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4355		WITH 2 SX CMT
PROD	5.5	4414	0	WITH 575 SX CMT
SURF	8.625	356		WITH 275 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/25/2018 1:30 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: RICK POPP Company: POPP OPERATING Phone: (620) 786-5514

Proposed Plugging Method: CIBP 50' ABOVE PERFS WITH 2 SX CMT. CIRCULATE CMT FROM 1500' TO SURFACE. TOP OFF & CHECK BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/25/2018 5:45 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4355' WITH 2 SX CMT. RUN TBG TO 1483' & MIXED 175 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 15 SX CMT. TIED ONTO BACKSIDE & PUMPED 5 SX CMT. PRESSURED TO 300#.

Perfs:

Top	Bot	Thru	Comments
4414	4430	OH	

INVOICED
AUG 03 2018

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
JUL 26 2018
KCC DODGE CITY

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

AUG 02 2018
CONSERVATION DIVISION
WICHITA, KS

kms