

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-20731-00-01  
Spot: SWSW Sec/Twnshp/Rge: 35-32S-10W  
667 feet from S Section Line, 4655 feet from E Section Line  
Lease Name: LAWRENCE Well #: 4  
County: BARBER Total Vertical Depth: 4940 feet

Operator License No.: 33235  
Op Name: CHIEFTAIN OIL CO., INC.  
Address: 101 S. 5TH ST. PO BOX 124  
KIOWA, KS 67070

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4310		WITH 2 SX CMT
PROD	5.5	4940	2700	WITH 175 SX CMT
SURF	8.625	360		WITH 123 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/19/2018 1:00 PM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SET CIBP @ 4330' & 2 SX CMT. PLUG AT 600' WITH 15 SX GEL & 50 SX CMT. PLUG AT 390' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/19/2018 2:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4310' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 608' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 384' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4410	4414		
4387	4393		

INVOICED

AUG 03 2018

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed Stephen J. Pfeifer  
(TECHNICIAN)

RECEIVED  
JUL 23 2018  
KCC DODGE CITY

RECEIVED  
KANSAS CORPORATION COMMISSION

AUG 02 2018

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

kms