

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-23681-00-00
Spot: NENWNWNE Sec/Twnshp/Rge: 31-24S-14W
4960 feet from S Section Line, 2088 feet from E Section Line
Lease Name: WILSON Well #: 31-31
County: STAFFORD Total Vertical Depth: 4431 feet

Operator License No.: 35510
Op Name: HOFFMAN RESOURCES LLC
Address: 165 WEST 1ST STREET PO BOX 387
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4422	2010	WITH 225 SX CMT
SURF	8.625	565		WITH 325 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/03/2018 2:30 PM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: DAVID BRADY Company: QUALITY OIL WELL CEMENTING Phone: (785) 483-2025

Proposed Plugging Method: SAND OR CIBP. PLUG AT 930' WITH 10 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/03/2018 6:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SAND BACK & TOP OFF WITH 5 SX CMT. TAGGED AT 4300'. 1ST PLUG AT 930' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT TO SURFACE. CMT HOLDING STEADY AT SURFACE.

Perfs:

Top	Bot	Thru	Comments
4364	4369		

INVOICED


AUG 03 2018

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED
JUL 24 2018
KCC DODGE CITY



RECEIVED
KANSAS CORPORATION COMMISSION

AUG 02 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

KMS