

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-151-22472-01-00  
Spot: SENWNESE Sec/Twnshp/Rge: 17-29S-12W  
2030 feet from S Section Line, 789 feet from E Section Line  
Lease Name: BRUBAKER Well #: 1-17H  
County: PRATT Total Vertical Depth: 4070 feet

Operator License No.: 31725  
Op Name: SHELBY RESOURCES LLC  
Address: 13949 W COLFAX AVE BLDG 1 STE 120  
LAKWOOD, CO 80401

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	13.375	345		

Well Type: LH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/06/2018 2:00 AM  
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.  
Proposal Rcvd. from: CHRIS GOTTSCHALK Company: SHELBY RESOURCES Phone: (720) 274-4682

Proposed Plugging Method: RIG CROWNED AND LOST COLLARS & PIPE DOWN HOLE. FISHED FOR 2 WEEKS. TOF @ 2894'. 1ST PLUG AT 2890' WITH 60 SX CMT. 2ND PLUG AT 780' WITH 60 SX CMT. 3RD PLUG AT 390' WITH 100 SX CMT. 4TH PLUG AT 60' WITH 30 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: NONE  
Date/Time Plugging Completed: 07/06/2018 4:00 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:

RIG CROWNED AND LOST COLLARS & PIPE DOWN HOLE. FISHED FOR 2 WEEKS. TOF @ 2894'. 1ST PLUG AT 2890' WITH 60 SX CMT. 2ND PLUG AT 780' WITH 60 SX CMT. 3RD PLUG AT 390' WITH 100 SX CMT. 4TH PLUG AT 60' WITH 30 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

INVOICED

AUG 03 2018

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: DP

District: 01

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED  
JUL 24 2018  
KCC DODGE CITY

RECEIVED  
KANSAS CORPORATION COMMISSION

Form CP-2/3

AUG 02 2018

CONSERVATION DIVISION  
WICHITA, KS