

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-21635-00-00  
Spot: NWSW Sec/Twnshp/Rge: 32-32S-10W  
1945 feet from S Section Line, 4578 feet from E Section Line  
Lease Name: TRAFFAS B Well #: 2  
County: BARBER Total Vertical Depth: 4617 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>31191</u>	CIBP		4370		WITH 2 SX CMT
Op Name: <u>R &amp; B OIL &amp; GAS, INC.</u>	PROD	4.5	4613	0	WITH 150 SX CMT
Address: <u>124 N MAIN PO BOX 195</u> <u>ATTICA, KS 67009</u>	SURF	8.625	244		WITH 175 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/05/2018 8:30 AM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: JEFF CAPP Company: SHAWNEE WELL SERVICE Phone: (620) 254-7251

Proposed Plugging Method: SET CIBP @ 4370' & 2 SX CMT. PERFORATE AT 600' & CIRCULATE CMT TO SURFACE INSIDE/OUTSIDE OF 4 1/2" CASING TO SURFACE.

Plugging Proposal Received By: KEN SCOFIELD Witness Type: PARTIAL  
Date/Time Plugging Completed: 07/05/2018 10:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

Perfs:

SET CIBP @ 4370' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. PERFORATE 4 1/2" CASING AT 600'. RUN TBG INTO 600'. PUMPED DOWN TBG WITH 200 SX CMT CIRCULATING CMT TO SURFACE INSIDE 4 1/2" X 8 5/8" ANNULUS.

Top	Bot	Thru	Comments
4332	4570		
4421	4422		


INVOICED  
AUG 03 2018

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed

  
(TECHNICIAN)

RECEIVED  
JUL 23 2018  
KCC DODGE CITY

RECEIVED  
KANSAS CORPORATION COMMISSION

Form CP-2/3

AUG 02 2018

CONSERVATION DIVISION  
WICHITA, KS

*km3*