

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-145-21745-00-00
Spot: NESENWSE Sec/Twnshp/Rge: 1-22S-16W
1785 feet from S Section Line, 1534 feet from E Section Line
Lease Name: WFY Well #: 1-1
County: PAWNEE Total Vertical Depth: 4000 feet

Operator License No.: 5205
Op Name: MID-CONTINENT ENERGY CORP.
Address: 105 S BROADWAY STE 360
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3900		
PROD	5.5	4002	0	WITH 275 SX CMT
SURF	8.625	937		WITH 550 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/10/2018 10:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: JEFF BURK Company: MID-CONTINENT ENERGY Phone: (316) 250-5655

Proposed Plugging Method: SET CIBP @ 3875' WITH 2 SX CMT. PERFORATE AT 980' & CIRCULATE CMT TO 0'.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: PARTIAL
Date/Time Plugging Completed: 07/10/2018 4:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

7/10/18: 2 3/8" TBG WAS AT 3925'. WELL WAS DIFFICULT TO KILL. WELL WAS BLOWN DOWN. TBG SHOT OFF AT 3880'. LEFT A SPENT TCG & 2 JOINTS 2 3/8" TBG IN HOLE. 1ST PLUG PUMPED AT 3880' WITH 75 SX COMMON CMT WITH 2% CC. 25 JOINTS PULLED & REVERSED OUT WITH 25 BBL WATER. CIRCULATED SMALL AMOUNT CMT & CMT COLORED WATER. SDON. 7/11/18: POOH WITH TBG. PERFORATE AT 980'. TIH WITH TBG TO 992'. ESTABLISH CIRCULATION UP 5 1/2" CASING AND ON ANNULUS.. PUMP 44 SX COMMON CMT & 200 SX 60/40 POZMIX 4% GEL. CMT CIRCULATED UP ANNULUS FIRST. VALVE ON BACK SHUT & CMT CIRCULATED TO SURFACE INSIDE 5 1/2" CSAING. POOH WITH TBG. TOP OFF CASING WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3925	3928		


INVOICED
AUG 03 2018

Remarks: USED COMMON CEMENT & 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed


(TECHNICIAN)

RECEIVED
JUL 24 2018
KCC DODGE CITY

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

AUG 02 2018
CONSERVATION DIVISION
WICHITA, KS

KMS