

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-12017-00-01
Spot: SESWNENE **Sec/Twnshp/Rge:** 32-24S-13W
993 feet from N Section Line, 698 feet from E Section Line
Lease Name: GLASSCOCK **Well #:** 1
County: STAFFORD **Total Vertical Depth:** 4233 feet

Operator License No.: 5205
Op Name: MID-CONTINENT ENERGY CORP.
Address: 105 S BROADWAY STE 360
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3960		WITH 2 SX CMT
PROD	5.5	4222	0	WITH 200 SX CMT
SURF	8.625	257		WITH 250 SX CMT

Well Type: OIL **UIC Docket No:** **Date/Time to Plug:** 07/03/2018 10:00 AM
Plug Co. License No.: 34059 **Plug Co. Name:** HURRICANE SERVICES, INC.
Proposal Rcvd. from: JEFFREY BURK **Company:** MID-CONTINENT ENERGY **Phone:** (316) 250-5655

Proposed Plugging Method: SET CIBP @ 3960' WITH 2 SX CMT. PERFORATE AT 870' WITH 50 SX CMT (200# HULLS IN LAST HALF). PERFORATE AT 300' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KENNY SULLIVAN **WitnessType:** COMPLETE (100%)
Date/Time Plugging Completed: 07/05/2018 9:00 AM **KCC Agent:** KEN SCOFIELD

Actual Plugging Report:

SET CIBP @ 3960' WITH 2 SX CMT PLACED ON TOP. PRESSURE TEST CASING TO 500 PSI FOR 2 MINUTES. PASSED. PERFORATE 5 1/2" CASING AT 870' & 300'. RIH WITH TBG TO 872' & BREAK CIRCULATION WITH FRESH WATER THEN PUMP 50 SX CMT WITH 150# HULLS IN LAST 25 SX CMT. PULL TBG TO 311' & PUMP 85 SX CMT TO FILL CASING & ANNULUS. 7/5/18: CMT FELL APPROXIMATELY 74'. TOPPED OFF WITH 15 SX CMT IN CASING & 6 SX CMT ON BACKSIDE.

Perfs:

Top	Bot	Thru	Comments
4004	4014		

INVOICED
AUG 03 2018

Remarks: USED 60/40 POZMIX 4% GEL BY HURRICANE SERVICES.

Plugged through: TBG

District: 01

Signed Kenny Sullivan

(TECHNICIAN)

RECEIVED
JUL 24 2018
KCC DODGE CITY

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 02 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

Kms