

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-057-20857-01-00  
Spot: SWSESESE Sec/Twnshp/Rge: 14-29S-25W  
223 feet from S Section Line, 348 feet from E Section Line  
Lease Name: STAGECOACH 2925 Well #: 1-14H  
County: FORD Total Vertical Depth: 5396 feet

Operator License No.: 35420  
Op Name: ELK ENERGY HOLDINGS LLC  
Address: 2250 N. ROCK RD. STE 118-107  
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5370		WITH 50 SX CMT
COND	20	128		WITH 16 SX CMT
	L1 4.5	9735		WITH 500 SX CMT
PROD	7	5832	1230	WITH 300 SX CMT
SURF	9.625	1183		WITH 430 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/11/2018 2:00 PM  
Plug Co. License No.: 35195 Plug Co. Name: SURE ENERGY SERVICE, LLC  
Proposal Rcvd. from: MARK MENDEZ Company: SURE ENERGY SERVICE, LLC Phone: (806) 228-6049

Proposed Plugging Method: CIBP @ 5370' WITH 50 SX CMT. PLUG AT 1250' WITH 15 SX GEL & 100 SX CMT. PLUG AT 660' WITH 50 SX CMT. PLUG AT 60' WITH 30 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/12/2018 6:15 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

7/11/18: SET CIBP @ 5370' WITH 50 SX CMT. 7/12/18: LAY DOWN 7" CASING.  
7/13/18: 1ST PLUG AT 1230' WITH 15 SX GEL & 100 SX CMT. 2ND PLUG AT 660'  
WITH 50 SX CMT. 3RD PLUG AT 60' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
8454	8788		
8055	8394		
7652	7960		
6766	7096		
6352	6720		
5970	6293		

INVOICED  
AUG 03 2018

Remarks: USED CLASS C CEMENT BY SURE ENERGY. TMD = 9780'.

Plugged through: TBG

District: 01

Signed \_\_\_\_\_

RECEIVED  
JUL 24 2018  
KCC DODGE CITY

RECEIVED (TECHNICIAN)  
KANSAS CORPORATION COMMISSION

AUG 02 2018

CONSERVATION DIVISION  
WICHITA, KS

lms