

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-057-20866-01-00
Spot: SWSESESE Sec/Twnshp/Rge: 26-29S-25W
214 feet from S Section Line, 513 feet from E Section Line
Lease Name: COACH 2925 Well #: 1-26H
County: FORD Total Vertical Depth: 5352 feet

Operator License No.: 35420
Op Name: ELK ENERGY HOLDINGS LLC
Address: 2250 N. ROCK RD. STE 118-107
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5325		WITH 50 SX CMT
COND 20		135		WITH 12 YDS CMT
L1 4.5		9790		TOP OF LINER 5378'
PROD 7		5843	1210	WITH 300 SX CMT
SURF 9.625		1097		WITH 405 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/19/2018 1:30 PM
Plug Co. License No.: 35195 Plug Co. Name: SURE ENERGY SERVICE, LLC
Proposal Rcvd. from: MARK MENDEZ Company: SURE ENERGY SERVICE, LLC Phone: (806) 228-6049

Proposed Plugging Method: CIBP @ 5370' WITH 50 SX CMT. PLUG AT 1230' WITH 15 SX GEL & 100 SX CMT. PLUG AT 650' WITH 50 SX CMT. PLUG AT 60' WITH 30 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/19/2018 3:25 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5325' WITH 50 SX CMT. 1ST PLUG AT 1580' WITH 30 SX CMT. 2ND PLUG AT 1140' WITH 15 SX GEL & 75 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 30 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
8106	8376		
7648	8004		
7250	7576		

INVOICED
AUG 03 2018

Remarks: USED CLASS C CEMENT BY SURE ENERGY. TMD = 9790'.

Plugged through: TBG

District: 01

RECEIVED
JUL 23 2018
KCC DODGE CITY

Signed 

RECEIVED (TECHNICIAN)
KANSAS CORPORATION COMMISSION

AUG 02 2018
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

KMS