

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-047-20342-00-00
Spot: SENWNWNE Sec/Twnshp/Rge: 18-24S-17W
421 feet from N Section Line, 2175 feet from E Section Line
Lease Name: GRYBOWSKI - MARTIN Well #: 1
County: EDWARDS Total Vertical Depth: 4490 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4300		WITH 2 SX CMT
PROD	4.5	4489	1268	WITH 150 SX CMT
SURF	8.625	252		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/18/2018 10:00 AM
Plug Co. License No.: 8253 Plug Co. Name: G & L WELL SERVICE, INC.
Proposal Rcvd. from: ROB LONG Company: F.G. HOLL Phone: (620) 793-0915

Proposed Plugging Method: CIBP @ 4300' WITH 2 SX CMT. PLUG AT 1230' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLGU AT 60' WITH 20 SX CMT TO SURFACE.

Plugging Proposal Received By: HEITH WALSH Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/18/2018 12:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

Perfs:

SET CIBP @ 4300' WITH 2 SX CMT PLACED ON TOP. 1ST PLUG AT 1230' WITH 10 SX GEL & 50 SX CMT. CIRCULATION ESTABLISHED HALF WAY THROUGH PUMPING GEL. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. CEMENT HOLDING WELL AT SURFACE.

Top	Bot	Thru	Comments
4355	4376		

INVOICED
AUG 03 2018

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
JUL 24 2018
KCC DODGE CITY

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 02 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

kms