

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-097-21669-00-01  
Spot: SENESSWSW Sec/Twnshp/Rge: 3-29S-18W  
831 feet from S Section Line, 995 feet from W Section Line  
Lease Name: MCKINLEY Well #: 1-3  
County: KIOWA Total Vertical Depth: 5500 feet

Operator License No.: 5056  
Op Name: F. G. HOLL COMPANY L.L.C.  
Address: 9431 E CENTRAL STE 100  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4753		WITH 2 SX CMT
PROD	4.5	5480	2490	WITH 190 SX CMT
SURF	8.625	690		WITH 300 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/12/2018 3:30 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 793-0915

Proposed Plugging Method: CIBP @ 4753' WITH 2 SX CMT. PLUG AT 1260' WITH 15 SX GEL & 50 SX CMT. PLUG AT 720 WITH 50 SX CMT. PLUG AT 360' WITH 30 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE  
Date/Time Plugging Completed: 07/12/2018 5:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4753' WITH 2 SX CMT. 1ST PLUG AT 1260' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 720' WITH 50 SX CMT. 3RD PLUG AT 360' WITH 30 SX CMT. 4TH PLUG AT 40' WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4855	4859		
4848	4853		
4838	4844		
4803	4811		

INVOICED  
AUG 03 2018

Remarks: USED 60/40 POZMX1 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED  
JUL 24 2018  
KCC DODGE CITY

RECEIVED  
KANSAS CORPORATION COMMISSION

Form CP-2/3

AUG 02 2018

CONSERVATION DIVISION  
WICHITA, KS

Kms