

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-20131-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 20-10S-24W
3630 feet from S Section Line, 2310 feet from E Section Line
Lease Name: GAY RUSH ESTATE C Well #: 2
County: GRAHAM Total Vertical Depth: 3960 feet

Operator License No.: 9067
Op Name: DAMAR RESOURCES, INC.
Address: 234 W 11TH STE A PO BOX 70
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3959		
SURF	8.625	174		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/24/2018 11:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: AVEN WEAVERLING Company: DAMAR RESOURCES, INC. DBA Phone: (785) 625-0020

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Perforations: 3753' - 3759', 3892' - 3895' and 3910' - 3914'

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/24/2018 6:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Shot perforations at 2600', 2020' and 1180'. Ran tubing to 3700' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 2950' and pumped 75 sx cement. Pulled tubing to 1950' and pumped 75 sx cement. Pulled tubing to 950' and pumped 75 sx cement. Good circulation of cement. Pulled tubing out. Topped off casing with 35 sx cement. Tied on to backside and squeezed with 50 sx cement.

GPS: 39.17089 -100.02324

Perfs:

Top	Bot	Thru	Comments
3794	3914		

Remarks: QUALITY CEMENT TICKET # 912

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

CM

JUL 30 2018

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 06 2018

CONSERVATION DIVISION
WICHITA, KS

INVOICED

AUG 06 2018

Form CP-2/3