

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-21396-00-00
Spot: NESENE Sec/Twnshp/Rge: 11-14S-15W
3630 feet from S Section Line, 330 feet from E Section Line
Lease Name: DUMLER C Well #: 12
County: RUSSELL Total Vertical Depth: 3330 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3329		125 SX
SURF	8.625	653		275 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/26/2018 10:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Revd. from: ALLEN BANGERT Company: MAI OIL OPERATIONS, INC. DBA Phone: (785) 483-2169

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls and 600 # gel.

Plugging Proposal Received By: BRUCE RODIE WitnessType: NONE
Date/Time Plugging Completed: 07/26/2018 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1375', 915' and 300'. Ran tubing to 3030' and pumped 6 sx gel followed by 100 sx cement w/200 # hulls. Pulled tubing to 1400' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 400'. Circulated cement to surface on casing with 90 sx cement. Circulated cement to surface on surface pipe with 90 sx cement. Pulled tubing and topped off with 20 sx cement.

Gps: 38.84902 -098.91604

Perfs:

Top	Bot	Thru	Comments
3074	3242		

Remarks: QUALITY OILWELL CEMENTING TICKET # 819

Plugged through: TBG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

RECEIVED
KANSAS CORPORATION COMMISSION

INVOICED

Form CP-2/3

JUL 30 2018

AUG 06 2018

AUG 06 2018

CONSERVATION DIVISION
WICHITA, KS