

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-23110-00-00
Spot: NENESWNW Sec/Twnshp/Rge: 30-11S-19W
3800 feet from S Section Line, 4170 feet from E Section Line
Lease Name: SCHONTHALER Well #: 3
County: ELLIS Total Vertical Depth: 3740 feet

Operator License No.: 34099
Op Name: RICHLAND OIL INVESTMENTS, LLC
Address: 608 E. 1ST PO BOX 166
PALCO, KS 67657

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3739		175 SX
SURF	8.625	258		140 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/24/2018 9:30 AM
Plug Co. License No.: 34266 Plug Co. Name: PRAIRIE HAWK WELL SERVICE LLC
Proposal Rcvd. from: BUTCH DRYLIE Company: RICHLAND OIL INVESTMENTS, LL Phone: (785) 324-2658

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls and 6 sx gel.
CIBP set at 3695'.
DV Tool set at 1485' w/375 sx H LC. Drilling mud was circulated out of well.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/24/2018 3:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3402' and pumped 3 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 2042' and pumped 75 sx cement w/300 # hulls. Pulled tubing to 945' and pumped 50 sx cement. Circulated 5 sx cement to the pit. POOH. Hooked to casing and pumped 20 sx cement. Casing was holding 400 psi. Hooked to braden head with 350#. No fluid moved.

GPS: 39.06953 -099.47755

Perfs:


Top	Bot	Thru	Comments
3701	3705		
3432	3438		

Remarks: GLOBAL CEMENTING TICKET # 3395

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

JUL 26 2018

AUG 06 2018

CONSERVATION DIVISION
WICHITA, KS

INVOICED
AUG 06 2018