

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
430 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-03443-00-00
Spot: E2E2NE Sec/Twnshp/Rge: 7-16S-13W
3960 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: HOFFMAN L Well Number: 2
County: BARTON Total Vertical Depth: 3371 feet

Operator License No.: 5088
Op Name: DARRAH, JOHN JAY, JR.
Address: 225 NORTH MARKET, STE 300
WICHITA, KS 67202

Conductor Pipe: Size _____ feet:
Surface Casing: Size 13.375 feet: 163
Production: Size 7 feet: 3364
Liner: Size _____ feet:

109.56

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/24/2001 9:00 AM
Plug Co. License No.: 5088 Plug Co. Name: DARRAH, JOHN JAY, JR.
Proposal Rcvd. from: GEORGE STOPPELWERTH Company: DARRAH, JOHN JAY, JR. Phone: (316) 263-2243

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 55 sxs gel spacer - 800# hulls.
Fluid Level 250'.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/24/2001 2:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Tied onto 7" and pumped 50 sxs cement with 400# hulls, followed by 28 sxs gel and 100# hulls, continued with 100 sxs cement.
Displaced to 200' with 8 bbls water.
Perforated casing at 200'.
Pumped to pressure with 100 sxs cement and 100# hulls.
Max. P.S.I. 900#. S.I.P. 400#.

INVOICED

DATE 4-27-01
2001061726

4-27-01

RECEIVED
STATE CORPORATION COMMISSION

APR 27 2001

CONSERVATION DIVISION

Remarks: ALLIED CEMENTING COMPANY.

Plugged through:

District: 04

Signed

Jay Pfeifer

(TECHNICIAN)

APR 25 2001