


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rice County, Sec. 21 Twp. 20 Rge. 10W (E) (W)
Location as "NE/CNW/SW" or footage from lines NW/SW/SE
Lease Owner Morgenstern & Spector
Lease Name Binger Well No. 1
Office Address Box 661, Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 3-23-49 19
Application for plugging filed Yes October 6, 1956 19
Application for plugging approved Yes October 8, 1956 19
Plugging commenced 10-18 19 56
Plugging completed 10-23 19 56
Reason for abandonment of well or producing formation failure to produce
profitably
If a producing well is abandoned, date of last production August 1956 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation Indian Cave Depth to top 2298 Bottom 2313 Total Depth of Well 2313 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7"	2301 ft.	1278'
				10 3/4"	120'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Measured into T.D. 2313'.
Plugging started 10-18-56. Finished 10-23-56.
Plugged off bottom with sand to 2290' and dumped 6 sacks cement.
Shot 7" casing at 1278'. Pulled pipe out of hole and plugged well with heavy mud to 175' and set permanent rock bridge. Dumped 30 sacks cement. Filled hole with heavy mud to 25' and mixed 5 sacks for cap on well.

10-31-56
RECEIVED
STATE CORPORATION COMMISSION
OCT 31 1956
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Company
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes
Box 221, Great Bend (Address)

SUBSCRIBED AND SWORN TO before me this 26 day of October, 1956

My commission expires April 8, 1957
Arthur J. Thibault Notary Public.

PLUGGING
FILE SEC 21 T. 20 R. 10W
BOOK PAGE 105 LINE 10


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - HUBER & PABCO
Farm - Binger No. 1

SEC. 21 T. 20 R. 10W
NW SW SE

Total Depth. 2313'
Comm. 2-4-49 Comp. 3-23-49
Shot or Treated.
Contractor. Pabco Drlg., Inc.
Issued. 4-23-49

County. Rice
KANSAS



CASING:
10-3/4" 120' Cem. W/100 Sx.
7" 2301' Cem. W/ 50 Sx.

Elevation. _____

Production. 50 BOPD

Figures Indicate Bottom of Formations.

shale & shells	115
shale & red bed	440
anhydrite	470
red bed	615
shale, salt & shells	1260
lime & sand	1340
lime	1440
lime & sand	1665
lime	1770
lime & shale	1960
shale	1995
lime & shale	2155
shale	2270
shale & lime	2298
sand	2313
Total Depth	

Top Sand 2298-2313, RTD
good show oil in samples

Set 7" at 2301' W/50 sx. Drilled
peeper to RTD. Ran tubing to test.
Testing for hole in 7" pipe. (no hole
found by test.) Ran wtr locator-no
results because of too much gas.
Caliper survey checked TD 2313 &
casing shoe at 2294. Swabbed
through 2" tubing 91 BO & 43
BW in 24 hrs. w/csgg pressure
increasing from 100# to 410#
at end of test. Completed for
50 BOPD W/trace wtr.

RECEIVED
STATE CORPORATION COMMISSION
OCT 6 1956
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 21 T. 20 R. 10W
BOOK PAGE 105 LINE 10

RECEIVED
STATE CORPORATION COMMISSION
OCT 8 X 1956
CONSERVATION DIVISION
Wichita, Kansas