


15-009-05 026-0000

DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION ~~SE 1/4~~ SW NE SE

SEC. 7 TWP. 16 RGE. 13 W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. _____ Lease McClanahan

Operator Pool & Handman Address Hickman - Kansas

Field _____ County Barton

Total Depth 3364 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/8 - 600 ft - Circulated with cement.
5/8 casing set at 3362 ft - Filled hole back from
bottom at 3110 ft with mud & Chat - Dumped 5 sacks
& cement at 3110 ft - Shot off & pulled the 5/8 casing
Filled with mud to 250 ft - Set Rock Bridge & 15 sacks
of cement at 250 ft - Mud to 30 ft - Plug & 10 sacks
of cement at the surface

JUL 14 1949

STAT. C. W. Stough
District Conservation Agent
KANSAS

Date 7-11-49

PLUGGING
SEC. 7 T. 16 R. 13 W
NO. 105. 10724