

15-009-034710000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 8 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Phillips Petroleum Company  
Complete Address Box 287, Great Bend, Kansas 67530  
Lease Name McClanahan Well No. # 3  
Location C N/2 N/2 SE Sec. 7 Twp. 16 Rge. 13 (E) (W) W  
County Barton Total Depth 3366  
Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A       
Other well as hereafter indicated       
Plugging Contractor Knight Casing Pulling Company  
Address Box 405, Chase, Kansas License No. # 436  
Operation Completed: Hour 10 A.M. Day 6 Month 9 Year 1972

The above well was plugged as follows:

10 3/4" csg. 593' Cwc.  
Sanded hole back to 3330' & dumped 5 sax cement with dump bailer. No pipe recovery.  
7" csg. previously squeezed. Mud to 620', set 20' rock bridge, & displaced 6 yds.  
Ready-mix Cement, cementing from 600' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Don L. Luman  
Well Plugging Supervisor

DATE 9/12/72  
INV. NO. 6296-11