


15 009 0346 90000

DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 139-8

LOCATION NE NE 1/4

SEC. 7 TWP. 16 RGE. 13W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease V. McClanahan

Operator Bethlehem Supply Address Box # 2171 Tulsa Okla

Field _____ County Barton

Total Depth 3377 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 625 ft. Circulated with cement
grouting set at 2363 ft. Filled back from
bottom to 3350 ft with shot. Dumped 9 sacks
of cement at 3342 ft. Shot off & pulled the grouting -
Filled with mud to 200 ft. Set Back Bridge & 20 sacks
of cement at 200 ft. Mud to 70 ft. Bridge &
10 sacks of cement at the surface.
Frank Carroll - Plugging Contractor

PLUGGING
FILE SEC 71 (Car 13a)
BOOK PAGE 139 LINE 2 FEB 25 1950

C. M. Strogg
District Conservation Agent

DATE 2-22-50

STATE CORPORATION
COMMISSION
KANSAS

2-25-50