

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 134-26

LOCATION SE-NE-NE

SEC. 2 TWP. 20 RGE. 11-w

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 13 Lease Feed Pumping "B"

Operator Stanolind Oil & Gas Co. Address Box #7 Elliswood-Kans.

Field _____ County Barton

Total Depth 3284 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 204 ft. Circulated with cement
6 casing out at 3273 ft - 100 sacks of cement - Plugged
back to 3260 ft. with sand & chat - Annulled 5 sacks of
cement at 3260 ft. - Shut off & pulled the 6 casing -
run to 204 ft. - Set back bridges & 20 sacks of cement
at 204 ft. - Run to 35 ft. - Bridges & 10 sacks of
cement at the surface!

The West Supply Co. - Plugging Contractors

PLUGGING
FILE SEC 2 T 20 R 11-w
PAGE 134 LINE 26

FILED
FEB 1 X 1952

C. W. Stouffer
District Conservation Agent

Date 1-30-52

2-1-52