

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 146-91

LOCATION E 1/2 - S 1/2 T 20 N R 11 W

SEC. 2 TWP. 20 RGE. 11 W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 16 Lease F. Panning

Operator Standard Oil Co. of Ind. Address Box #7 Elliptical - Kans.

Field \_\_\_\_\_ County Barton

Total Depth 3280 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 10 3/4 - 200 ft. Circulated with cement.  
C casing set at 3273 ft. Plugged back to 3260 ft  
with chert. Dumped 6 sacks of cement at 3260 ft -  
Shot off & pulled the c casing - Filled with sand to 245 ft  
Back Bridge & 20 sacks of cement at 245 ft - sand  
to 30 ft - Bridge & 10 sacks of cement  
at the surface -  
Pipe Pulling, Inc. Plugging Contractors*

MAY 18 1950 5-18-50

STATE CORPORATION

*C. H. Stough*  
District Conservation Agent

Date 5-19-50

**PLUGGING**  
FILE SEC. 2 T 20 R 11 W  
BOOK PAGE 146 LINE 81