

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 34-8LOCATION NE-SE-NWSEC. 2 TWP. 20 RGE. 11-WDry Hole Abandoned Oil Well X Abandoned Gas Well

I have today completed supervision of plugging of:

Well No. 5 Lease A.P. Schartz - "A"Operator Stanford Oil & Gas Co Address Box #7 - Ellinwood - Kans.Field County BartonTotal Depth 3304 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 $\frac{3}{4}$ - 217 ft. Circulated with cement
6" casing set at 3273 ft. & cemented with 100 sacks cement
Plugged back to 3260 ft. with sand - Plugged 5 sacks
of cement at 3260 ft. - Ripped off & Pulled the
6" casing - Mud to 217 ft. - Put Rock Bridge
& 20 sacks of cement at 217 ft. - Mud to 30 ft
Plug & 10 sacks of cement at the surface -
Rex S. Pile Pulling Co. Plugging Contractor

RECEIVED
STATE CORPORATION COMMISSION

NOV 20 1950

CONSERVATION DIVISION

Wichita, Kansas

District Conservation Agent

Date 11-17-50