

B

TO:

FILE NO. 113-5

LOCATION Sw-Sw-Nw

SEC. 2 TWP. 20 RGE. 11 W

Dry Hole Abandoned Oil Well ✓ Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 6 Lease Schary "A"

Operator Standard Oil & Gas Co. Address Box 7, Ellinwood K.

Field _____ County Boston

Total Depth 3302 Feet.

Plugging Contractor - West Supply Co., Inc.

Plugging Contractor's License No. 14

Address Chase, Kansas

(Describe briefly the manner in which the well was plugged)

Surface pipe 10 $\frac{3}{4}$ " @ 200' C.W.C. 6" O.D. set
3240' w/ 100 sx Cem. Sand to 3280' dump 5 sx Cem.
Shot off and pulled 6" casing. Filled
hole with heavy mud to 225' set rock
bridge and dumped 25 sx Cem. mud to
30' rock bridge and 10 sx Cem. to base
of Cellar

RECEIVED
STATE CORPORATION COMMISSION
MAY 16 1955
CONSERVATION DIVISION
5

Warren H. Horner
District Conservation Agent

Date May 13, 1955

2-20-11W

PLUGGING

FILE SEC 36 T 21 R 14W

BOOK PAGE 109 LINE 40

113-5