

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 48-85LOCATION C. 17 1/2 - 27 1/2 - 22 WSEC. 2 TWP. 20 RGE. 11-WDry Hole Abandoned Oil Well X Abandoned Gas Well

I have today completed supervision of plugging of:

Well No. 12 Lease A. SchwartzOperator Standard Oil & Gas Co. Address Box #7 - Ellinwood - Kans.Field County BartonTotal Depth 3301 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/4 - 226 ft. Circulated with cement.
9 1/2" casing set at 3285 ft. Cemented with 75 sacks cement.
Plugged back to 3275 ft. with chat - Mixed 5 sacks
of cement at 3275 ft. - Ripped off & pulled the 9 1/2" casing
Up to 226 ft. - Set Rock Bridge & 15 sacks of
cement at 226 ft. - Mud to 30 ft. - Plug &
10 sacks of cement at the surface.
A & S Pipe Plugging Co. - Plugging Contractor

RECEIVED
STATE CORPORATION COMMISSION

JAN 16 1951

CONSERVATION DIVISION

Wichita, Kansas

District Conservation Agent

Date 1-14-51