

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 61-84

LOCATION QSW/4-

SEC. 2 TWP. 10 RGE. 11-w

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 14 Lease A. Schwartz

Operator Standard Oil & Gas Co Address Box #7 - Elmwood - Mans-

Field \_\_\_\_\_ County Barton

Total Depth 3306 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 235 ft. Circulated with cement.  
5 1/2" casing set at 3293 ft. Cemented with 75 sacks of  
cement. Plugged back to 3290 ft with chert - 5 sacks  
of cement dumped at 3290 ft. Shot off & pulled  
the 5 1/2" casing - Filled hole with mud to 235 ft.  
Set Rock Bridge & 15 sacks of cement at 235 ft.  
Mud to 30 ft. Plug & 10 sacks cement at the surface.  
West Supply Co. - Plugging Contractors

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 24 1951

**PLUGGING**  
FILE SEC 2 T 10 R 11W  
BOOK PAGE 61 LINE 24

C. M. Stone District Conservation Agent  
Wichita, Kansas  
Date 2-22-51