

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 13 1975  
CONSERVATION DIVISION  
Wichita, Kansas

3-13-75

Operator's Full Name Mapco, Inc.

Complete Address 1437 S. Boulder, Tulsa, Oklahoma 74119

Lease Name Schurr Well No. 1

Location C SW Sec. 21 Twp. 20 Rge. 10 (E) (W) X

County Rice Total Depth 2554'

Abandoned Oil Well          Gas Well          Input Well          SWD Well          D & A X

Other well as hereafter indicated         

Plugging Contractor Red Tiger Drilling Company

Address 1720 Wichita Plaza, Wichita, Kansas License No.         

Operation Completed: Hour 1:30 AM Day 11 Month March Year 1975

The above well was plugged as follows:

Hole filled with mud. Plug pushed to 500' and 40 sacks cement pumped  
through drill pipe at 500'. 25 sacks cement pumped through drill pipe  
at 240'. Plug and 1/2 sack hulls pushed to 40' and hole cemented with  
10 sacks cement to base of cellar. Rathole bridged and cemented with  
2 sacks cement.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 3/13/75

INV. NO. 1008-W