

State of Kansas



15.009.14329.0000

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

OCT 17 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. O. C. Arnott of Jay Bergman Oil Company has this date requested permission to plug the following described well:

Mr. Harold Bergman guarantees payment of the plugging fee.

Operator's full Name: Jay <sup>Bergman</sup> Panning Oil Company

Complete Address: 425 Union Center, Wichita, Kansas

Lease Name: Panning Well No. # 8

Location: NE SW SE Sec. 3 Twp. 20 Rge. 11 (E)(W) W

County Barton Total Depth 3302 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. R. E. Smith was instructed to plug the well as follows:

8 5/8" 158' Cwc.

Sanded hole back to 3285' & dumped 5 sax cement with dump bailer.

Pulled pipe. Mudded hole to 160', set rock bridge, & displaced

5 sax cement with dump bailer. Let over night, bailed hole dry, &

displaced 20 sax cement. Mud to 40', set rock bridge, & displaced

10 sax cement, cementing to base of <sup>cellar.</sup> well.

Very truly yours,

*Don Truman*  
Conservation Division Agent