

State of Kansas



15.009.14339.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION

OCT 7 1974

CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Orville Monroe of Clinton Oil Company has this
date requested permission to plug the following described well:Mr. Clinton Oil Company guarantees payment of the plugging fee.Operator's full Name: Clinton Oil CompanyComplete Address: P. O. Box 1201, Wichita, Kansas 67201Lease Name: Charles Rose Well No. # 2Location: NE NE NE Sec. 3 Twp. 20 Rge. 11 (E)(W) WCounty: Barton Total Depth 3294 Oil Well XXGas Well Input Well SWD Well D & A Lost Hole Mr. Jim Gillespie was instructed to plug the well as follows:10 3/4" csg. 191' Cwc.Sanded hole back to 3250' & dumped 5 sax cement with dump bailer.Pulled pipe. Squeezed well with 2 sax hulls, 20 sax mud, 1 sax hulls.& displaced 125 sax cement with Sun Cementing Company's pump truck,cementing from 320' to base of cellar.

Very truly yours,

Conservation Division Agent