



15.009.19545.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 7 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Orville Monroe of Clinton Oil Company has this
date requested permission to plug the following described well:

Mr. Clinton Oil Company guarantees payment of the plugging fee.

Operator's full Name: Clinton Oil Company

Complete Address: P. O. Box 1201, Wichita, Kansas 67201

Lease Name: Charles Rose Well No. # 4

Location: C E/2 E/2 NE Sec. 3 Twp. 20 Rge. 11 (E)(W) W

County: Barton Total Depth 3287 Oil Well XX

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Jim Gillespie was instructed to plug the well as follows:

8 5/8" csg. 232' Cwc.

Sanded hole back to 3250' & dumped 5 sax cement with dump bailer.

Pulled pipe. Squeezed well with 3 sax hulls, 20 sax mud, released

plug, & displaced 100 sax cement with Sun Cementing Company's pump truck,
cementing from 320' to base of cellar.

Very truly yours,

Don Lunsford
Conservation Division Agent