

State of Kansas



WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED
 STATE CORPORATION COMMISSION

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

MAR 15 1967

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Dear Sir:

Mr. Voet of Colorado Oil Co. has this

date requested permission to plug the following described well:

Mr. Voet guarantees payment of the plugging fee.

Operator's full Name: Colorado Oil Co.

Complete Address: 915 Union Nat'l. Bldg. Wichita, Kansas

Lease Name: ~~Byne~~ Ryno Well No. # 1

Location: NE NW NW Sec. 6 Twp. 19 Rge. 1 (E) (W)

County McPherson Total Depth 3715' Oil Well

Gas Well Input Well SWD Well X D & A Lost Hole

Mr. Voet was instructed to plug the well as follows:

8 5/8" - 105' - Circulated w/cement, 3581' - 5 1/2" - Cemented.

Tubing in hole, from 3715' to 2550'. Bridge 2550' to 1800'.

10 Sax. cement 1800' to 1730'. Mud 1730' to 150'.

Bridge 150' to 140'. 25 Sax. cement 140' to 65'. Mud 65' to 40'.

Bridge 40' to 30'. 10 Sax. cement 30' to 0.

Very truly yours,

Hugh Scott
 Conservation Division Agent