



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 8 1972

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. A. T. Slagle of Phillips Petroleum Co. has this
date requested permission to plug the following described well:

Mr. Phillips Petroleum Co. guarantees payment of the plugging fee.

Operator's full Name: Phillips Petroleum Company

Complete Address: Box 287, Great Bend, Kansas 67530

Lease Name: McClanahan Well No. # 3

Location: C N/2 N/2 SE Sec. 7 Twp. 16 Rge. 13 (E)(W) W

County: Barton Total Depth 3366 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Mike Wassinger was instructed to plug the well as follows:

10 3/4" csg. 593' Cwc.

Sanded hole back to 3330' & dumped 5 sax cement with dump bailer. No

pipe recovery. 7" csg. previously squeezed. Mud to 620', set 20' rock

bridge, & displaced 6 yds. Ready-mix Cement, cementing from 600' to

base of cellar.

Very truly yours,

Don L. Lewis
Conservation Division Agent