

State of Kansas



15.009.14281.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027

3830 S. Meridian

WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 1 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Orville Monroe of Clinton Oil Company has this

date requested permission to plug the following described well:

Mr. Clinton Oil Company guarantees payment of the plugging fee.

Operator's full Name: Clinton Oil Company

Complete Address: 217 North Water, Wichita, Kansas 67202

Lease Name: Wm. Panning Well No. # 2

Location: NW NW SE Sec. 2 Twp. 20 Rge. 11 (E)(W) W

County: Barton Total Depth 3292 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Noel Knight was instructed to plug the well as follows:

10 3/4" csg. 188' Cwc. Perf. 3015'

Sanded hole back to 3000' & dumped 5 sax cement with dump bailer.

Pulled pipe. Squeezed well with 15 sax mud, 75 sax cement, 5 sax

mud, 1 sax hulls, & 25 sax cement with Allied Cementing Company's

pump truck, cementing from 300' to base of cellar.

Very truly yours,

D. W. Lusk
Conservation Division Agent