

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rice County. Sec. 17 Twp. 20S Rge. 10 (E/W) (W)

Location as "NE/CNW/SW" or footage from lines NE NW NE

Lease Owner Giles & Olsson

Lease Name Poncin Well No. 1

Office Address 353 Armour, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed January 28 1964

Application for plugging filed January 28 1964

Application for plugging approved January 28 1964


Plugging commenced January 28 1964

Plugging completed January 28 1964

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Name of Conservation Agent who supervised plugging of this well Gilbert J. Toman

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3407 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 217 | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled with ;mud to 210 feet. Plug and 1/4 sack hulls pushed to 210 feet and hole cemented with 20 sacks through drill pipe.
Hole filled with mud to 40 feet. Plug and 1/4 sack hulls pushed to 40 feet and hole cemented to base of cellar with 10 sacks cement.

Rat hole bridged and ;cemented with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

NOV 18 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Burt Drilling Company
Address 1823 Washington, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Duke C. Burt (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Duke C. Burt

1823 Washington, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of November, 19 65

My commission expires October 15, 1967

Notary Public.

GILES & OLSSON
Great Bend, Kansas

Well: Poncin No. 1
Commenced R.D.: 1/17/64
Completed R.D.: 1/28/64
Total Depth: 3,407' D.F.
Casing: 217' of 8 5/8" 8 rd thd 24#

Sec. 17-20-10W
Rice County, Kansas
Elevation:
Initial Prod: D & A
Contractor: BURT DRILLING
COMPANY

| Strata | Depth |
|----------------------|-----------|
| Sand & shale | 0- 217' |
| Shale & shells | 217- 475 |
| Anhydrite | 475- 505 |
| Shale & shells | 505-1305 |
| Shale & lime Streaks | 1305-1950 |
| Lime & shale | 1950-2080 |
| Shale & lime streaks | 2080-2250 |
| Shale, lime & sand | 2250-2409 |
| Shale w/lime streaks | 2409-2650 |
| Lime | 2650-2930 |
| Hubner Shale | 2930-2934 |
| Lime | 2934-2960 |
| Shale | 2960-3054 |
| Lime (Lansing 3054) | 3054-3360 |
| Lime & shale | 3360-3391 |
| Lime | 3391-3407 |

NOV 18 1965
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above is a true and correct log of said well as reflected by daily reports.

BURT DRILLING CO.

[Signature]

Signed and sworn to in my presence this 16th day of November, 1964.

[Signature]
Notary Public

My Commission Expires: October 15, 1967