

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas



NORTH

			.5

Locate well correctly on above
Section Plat

Rice County. Sec. 18 Twp. 20 Rge. (X) 10 (W)
Location as "NE/CNW/SW" or footage from lines C-N/2 NE NE
Lease Owner Sohio Petroleum Company
Lease Name Mantel #5 Well No. 5
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed August 1, 19 46
Application for plugging filed September 20 19 57
Application for plugging approved September 24 19 57
Plugging commenced October 21 19 57
Plugging completed October 25 19 57
Reason for abandonment of well or producing formation subject well had reached its economic limit.

If a producing well is abandoned, date of last production February 13, 19 57
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Ruel Durkee, McPherson, Kansas
Producing formation Arbuckle Depth to top 3328' Bottom 3338' Total Depth of Well 3340' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lansing-Kansas City		3020'		8-5/8"	172'	none
Arbuckle		3328'	3340'	5-1/2"	3330'	2494.50'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

3340' to 3310' 50 gallons of sand dumped.
6 sacks of cement dumped.
3310' to 162' Mudded hole and set rock bridge at 162'.
162' to 20' Dumped 15 sacks of cement and mudded hole to 20'.
20' to cellar Rock bridge and dumped 5 sacks of cement into bottom of floor cellar.

RECEIVED
STATE CORPORATION COMMISSION

10-30-57 OCT 30 1957

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
J. H. Bond (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. H. Bond
(Address) _____

SUBSCRIBED AND SWORN TO before me this 29th day of October, 1957

My Commission Expires July 2, 1961

Russell Miller
Notary Public.

My commission expires _____

PLUGGING
FILE SEC. 18 T. 20 R. 10 W
BOOK PAGE 47 LINE 16

Mantel #5
 C-N/2 NE NE
 Section 18-20S-10W
 Rice County, Kansas

Commenced: 1-12-46
 Completed: 3-27-46

Surface	172'
Red bed, shale and shells	640'
Shale and shells	970'
Salt and shells	1125'
Shale and shells	1150'
Shale and lime	1805'
Shale and shells	2250'
Shale and lime	2630'
Lime - broken	2800'
Lime	2890'
Lime - broken	3330'
Lime	3335'
Cored	3340' T.D.

Casing Record

8-5/8" casing set at	172'
5-1/2" casing set at	3330'

FILE SEC 18 T. 20 R. 10W
 BOOK PAGE 47 LINE 16

RECEIVED
 STATE CONSERVATION COMMISSION
 SEP 23 1957
 CONSERVATION DIVISION
 Wichita, Kansas