


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rice County, Sec. 18 Twp. 20S Rge. (E) 10(W)
SW/SW/NE
Location as "NE/CNW/SW" or footage from lines
Lease Owner Spector and Morganstern
Lease Name Maggie Hirsh Well No. 4
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed 5-26-48 19
Application for plugging filed August 5 19 55
Application for plugging approved August 8 19 55
Plugging commenced 8-25- 19 55
Plugging completed 8-31- 19 55
Reason for abandonment of well or producing formation Failed to produce profitably.
If a producing well is abandoned, date of last production Aug. 19 55
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ruel Duerke
Producing formation Arbuckle Depth to top 3275 Bottom 3276 Total Depth of Well 3277 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	451'	XXXX none
				5 1/2	3276'	2590'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugging started 8-25-55 and completed 8-31-55. Plugged off bottom with rock back to 3270' and dumped in 6 sacks of cement. Shot casing off at 2590' and pulled pipe out of hole. Filled hole with heavy mud to 190', set permanent rock bridge, dumped in 15 sacks of cement, and filled hole with heavy mud to 25' of top, set permanent rock bridge and dumped in 5 sacks of cement for cap on well.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Forbes Casing Pulling Co. d/b/a J. O. Forbes
Address P. O. Box 221, Great Bend, Kansas

STATE OF Kansas COUNTY OF Russell, ss.
Morgenstern & Spector (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Morganstern*
Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 6th day of September, 1955

My commission expires Dec 1, 1955
Elicia Candy Notary Public.

PLUGGING
FLX SEC 18 T20 R10W
BOOK PAGE 144 LINE 21

RECEIVED
STATE CORPORATION COMMISSION
SEP 2 1955
CONSERVATION DIVISION
7-8-55

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company - GULF OIL CORPORATION
Farm - Maggie Hirsh "A" No. 4

SEC. 18 T. 20S R. 10W
SW SW NE ; 2260' S NL
& 330' E WL of NE/4

Total Depth. 3283'
Comm. 5-7-48 Comp. 5-26-48
Shot or Treated. acidized w/500 gals. 5-25-48
Contractor.
Issued. 8-14-48

County. Rice

KANSAS



CASING: 8 5/8" @ 451'; cem. w/200 sacks
5 1/2" @ 3276'; cem. w/100 sacks

Elevation. _____

Production. 290 BO no wtr.

Figures Indicate Bottom of Formations.

shaley sand	70
shale & red bed	390
red rock	435
lime	451
red bed & shale	1000
shale & shells	1120
salt	1220
shale & shells	1255
lime	1795
shale & lime	1925
lime & shale	2530
shale	2630
lime	2860
shale	3005
lime & shale	3271
lime	3277
Total Depth	

Deepened with cable tools 3283 T.D.

Original hole located Center SW SW NE of Section 18-20S-10W, Rice County, Kansas, was lost at a depth of 2320' due to being unable to recover drill pipe twisted off at 1150'. 8 5/8" casing was cemented at 450', none of which was recovered. Plugging of the hole was completed 5-10-48.

Tops:

Heebner	2859
Brown Lime	2980
Lansing-Kansas City	3001
Arbuckle	3275

PLUGGING
FILE SEC. 18 T. 20 R. 10W
BOOK PAGE 114 LINE 21

RECEIVED
STATE CORPORATION COMMISSION

AUG 25 1955

CONSERVATION DIVISION
Wichita, Kansas