

WELL PLUGGING RECORD

NORTH


Locate well correctly on above Section Plat

Rice County. Sec. 8 Twp. 20 Rge. 10 (E) W (W)  
 Location as "NE/CNW/SW" or footage from lines SW SE NW  
 Lease Owner West Supply Co., Inc.  
 Lease Name Farke #1 SWD Well No. \_\_\_\_\_  
 Office Address Chase, Kansas  
 Character of Well (completed as Oil, Gas or Dry Hole) SWD. Well  
 Date well completed \_\_\_\_\_ 19\_\_\_\_  
 Application for plugging filed 8-12-57 19\_\_\_\_  
 Application for plugging approved 8-14-57 19\_\_\_\_  
 Plugging commenced 9- 5-57 19\_\_\_\_  
 Plugging completed 9- 7-57 19\_\_\_\_  
 Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3849 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	216'	none
				7"	3630'	1428'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked the hole to 3849' and found it open.  
 Checked fluid to 460'. Mudded the hole from 3849' to 3620'. Pulled 7" casing. Checked hole and found fluid down. Mudded the hole to 200', set a rock bridge and ran 20 sacks of cement. Mudded the hole to 15', set a rock bridge and ran 5 sacks of cement to base of cellar.

RECEIVED  
 CORPORATION COMMISSION  
 SEP 12 1957  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor West Supply Co., Inc.  
 Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.  
 \_\_\_\_\_ (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 10th day of September, 19 57

(Address)

Thomas V. Duggin

Notary Public.

My commission expires 9-27-58

PLUGGING  
 FILE SEC 8 T 20 R 10 W  
 BOOK PAGE 35 LINE 44


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY,  
412 Union National Bank Bldg, Wichita, Kansas.

PHILLIPS PETRO. CO.  
Clara Park No. 1.

SEC. 8 T. 20 R. 10W.  
SW SE NW

Total Depth. 3885 1/2 SLM  
Comm. 5-26-37 Comp. 9-1-37  
Shot or Treated.  
Contractor.  
Issued. 11-20-37

County ~~Barton~~ Rice



CASING.

10" 203'  
7" 3604

Elevation.  
Water.  
Production. Disposal Well.

Figures Indicate Bottom of Formations.

surface soil	35
shaly shale	250
broken lime and shale	595
shale and shells	1025
salt	1155
shale and lime	1420
lime	1590
broken limo	1725
lime	1860
shale	2040
lime	2140
shale	2170
limo	2370
shale	2585
limo	2635
shale	2685
broken lime	2755
lime	2975
shale	3050
lime	3140
lime cored	3155
limo	3180
shale	3287
conglomerate	3310
lime	3317
conglomerate	3322
lime	3440
broken limo	3445
lime	3450
lime cored	3455
limo	3486
shale	3512
limo	3626
lime and shale	3761
limo	3900
Corrected total depth.	3885 1/2 SLM.

Total Depth.

Completed for wtr disposal well.  
took 960 bbls in 1 hr and 40 min.

RECEIVED  
STATE SURVEY DIVISION

PLUGGING  
FILE SEC 8 T. 20 R. 10W  
BOOK PAGE 35 LINE 44

AUG 15  
CONSERVATION DIVISION  
WICHITA, KANSAS


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

PHILLIPS PETRO. CO.  
Clara Park No. 1.

SEC. 8 T. 20 R. 10W.  
SW SE NW

Total Depth. 3885 $\frac{1}{2}$  SLM  
Comm. 5-26-37 Comp. 9-1-37  
Shot or Treated.  
Contractor.  
Issued. 11-20-37

County Rice



CASING.

10" 203'

7" 3604

Elevation.  
Water.  
Production. Disposal Well.

Figures Indicate Bottom of Formations.

surface soil	35
shaly shale	250
broken lime and shale	595
shale and shells	1025
salt	1155
shale and lime	1420
lime	1590
broken lime	1725
lime	1860
shale	2040
lime	2140
shale	2170
lime	2370
shale	2585
lime	2635
shale	2685
broken lime	2755
lime	2975
shale	3050
lime	3140
lime cored	3155
lime	3180
shale	3287
conglomerate	3310
lime	3317
conglomerate	3322
lime	3440
broken lime	3445
lime	3450
lime cored	3455
lime	3480
shale	3512
lime	3626
lime and shale	3761
lime	3900
Corrected total depth.	3885 $\frac{1}{2}$ SLM.

Total Depth.

Completed for wtr disposal well.  
took 960 bbls in 1 hr and 40 min.

RECEIVED  
STATE COM. & REG. CO.  
SEP 6 1957  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 8 T. 20 R. 10W.  
BOOK PAGE 35 LINE 44