


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit,
Mail or Deliver Report to:
Conservation Division,
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

NORTH



Locate well correctly on above
Section Plat

~~1039~~Rice County, Sec. 8 Twp. 20 Rge. 10 (E) (W)
SW SE SW
Location as "NE/CNWxSWx" or footage from lines
Lease Owner K & K Production
Lease Name Bayer #1 Well No.
Office Address Chase, Kansas 67524
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 7/28/70 19
Plugging completed 7/31/70 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman
Producing formation Depth to top Bottom Total Depth of Well 3375 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	202	none
				5 1/2"	3368	3002'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.


Checked hole, ran sand to 3350' and ran 5 sacks of cement.
Loaded hole with water, shot pipe at 3007', pulled 91 joints.
Pumped 13 sacks mud, 60 sacks cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
AUG 7 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) [Signature]
CHASE, KANSAS (Address)

Subscribed and sworn to before me this 5th day of August, 1970

[Signature]
Notary Public.

My commission expires 2/15/71

THUNDERBIRD DRILLING INC.

WELL COMPLETION REPORT

DATE	TIME	WELL	Bayer #1	SEC: 8	TWP: 20	RGE: 10	LOC: SW/SE/SW
		COUNTY	Rice	STATE	Kansas	POOL	Silica
19 56		ELEV: KB:	1812	DF:	1809	GL:	1807
Moved In		ROTARY CONTRACTOR	Thunderbird Drilling Inc. Rig #1				
Moved In		CABLE TOOL CONTRACTOR	Dover Drilling Co. Rig #1				
5-5		SURFACE CASING	Sax				
		Size	8 5/8" It	28# Lgth	202	Cement	140 % Gal 1 CC 200#
		PRODUCTION STRING	Sax				
4-28	9:15 P	Size	5 1/2" Wt	14 Grade	J-55	Cerent	50 % Gal 2 Other
PIPE SETTING SUPERVISED BY Daniel				TYPE BRADEN HEAD Walker L-8			
TYPE FLOAT COLLAR Baker Flexiflow				TYPE SHOE Larkin Guide			
SCRATCHER PLACEMENT 3357-67							
CENTRALIZER PLACEMENT None							
ALL MEASUREMENT IS FROM ROTARY KELLY PUSHING::: ZERO POINT 8.10 above bradenhead							
OTHER CASING EQUIP:							

CASING JOINTS FROM FLOAT COLLAR UP	33.29	32.28	33.84	28.02	33.67	32.80	33.82
	33.27	32.38	28.53	33.25	33.86	33.81	33.73
	32.02	33.82	33.90	32.77	33.78		

RTD 3375	CAS SET 3368	SHOE JT 28.50	FLOAT COLLAR 3339.50
TOP Arb	FOR ATION 3366	TOP ANHYDRITE	BOTTOM ANHYDRITE
CASING MEASUREMENT ON TD 3371.75		DRILL PIPE STRAPPING ON TD 3374.91	
TOP CEMENT ROOM TEMPERATURE SURVEY			
OTHER DATA:			

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 30 1970
 CONSERVATION DIVISION
 Wichita, Kansas

