

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Rice

County. Sec. 8 Twp. 20S Rge. 10W (E) (W)

Location as "NE/CNW/SE/SW" or footage from lines Tomlinson & Kathol

Lease Owner \_\_\_\_\_

Lease Name Bayer

Well No. 2

Office Address 1125 Wichita Plaza, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 2/13 1964

Application for plugging filed 2/13 1964

Application for plugging approved 2/13 1964

Plugging commenced 2/13/64 1964

Plugging completed 2/13/ 1964

Reason for abandonment of well or producing formation No commercial quantities of oil or gas encountered

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH


Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation None Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3416 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface				8-5/8"	170'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud was introduced into the hole to a depth of 160 feet where the bottom plug was set and cemented with 20 sacks cement. Mud was again put into the hole to a depth of 40 feet where the top plug was set and cemented with 10 sacks cement. Rat Hole was plugged with 2 sacks cement. Surface casing was cut off below ground level and the location abandoned.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 20 1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Tomlinson-Kathol, Inc.

Address 1125 Wichita Plaza, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Richard C. Davis

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Richard C. Davis  
1125 Wichita Plaza, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of February, 19 64

Ester L. Lamm

Notary Public.

My commission expires January 19, 1965



DRILLERS LOG  
 TOMLINSON & KATHOL  
 # 2 BAYER  
 NE NE SW, Sec. 8-20S-10W  
 RICE COUNTY, KANSAS

RECEIVED  
 STATE CORPORATION COMMISSION

FEB 20 1964

CONSERVATION DIVISION  
 Wichita, Kansas

Contractor - Tomlinson-Kathol, Inc.

Commenced: 2/5/64  
 Completed: 2/13/64  
 Elevation: 1816 KB


<u>From</u>	<u>To</u>	<u>Description</u>	<u>Remarks</u>
0	150	Sand and sandy clay	
150	170	Sandy clay and shale	
170	702	Shale and shells	170' 8-5/8" Surf. Csg. w/150 sacks
702	1332	Shale & Shells	
1332	1510	Shale	
1510	1680	Shale & Lime	
1680	1860	Lime & Shale	
1860	1983	Shale & Lime	
1983	2480	Shale	
2480	2607	Lime & Shale	
2607	2843	Shale & Lime	
2843	2939	Lime & Shale	
2939	3089	Shale	
3089	3321	Lime & Shale	Heebner 2941
3321	3385	Lime	Toronto 2965
3385	3416	Arbuckle	Douglas 2973
3416		Total Depth	Brown Lime 3065
			Lansing 3095
			Base K.C. 3350
			Arbuckle 3382

I certify to the best of my knowledge and belief, the above represents a true and accurate driller's log record of the captioned well.

  
 Richard C. Davis, Geologist

STATE OF KANSAS  
 SS  
 COUNTY OF SEDGWICK

Subscribed and sworn to before me this 18th day of February, 1964.

  
 Esther Lamone, Notary Public

My Commission Expires: 1/19/65